

## SCHEDULE 1

### PART 1

#### Authorised development

##### **In the County of Flintshire**

*Work No. 29:* Construction of an underground Carbon Dioxide (CO<sub>2</sub>) pipeline approximately 625 metres in length and with an external diameter of 36 inches (914.4 millimetres) between Work No. 28 and Work No. 30 including—

- (a) construction and installation of the pipeline by trenched and untrenched methods, including trenchless installation technique pit works, the creation of reception shafts, and launch shafts, and installation of concrete-lined sleeve tunnels;
- (b) installation of pipeline marker posts and cathodic protection test posts along the pipeline route;
- (c) installation of underground telecommunications cable;
- (d) construction of a haul road, temporary construction accesses and working areas and laydown area;
- (e) landscaping, ecological and environmental works; and
- (f) drainage works including creation of connections to existing drainage and creation of new sustainable drainage systems including attenuation pond(s);