SCHEDULES

SCHEDULE 14

Article 28

Deemed licence under the 2009 Act – interconnection (licence 1 – phase 1)

PART 1

Licensed marine activities

1.—(1) In this licence—

"the 2004 Act" means the Energy Act 2004(1);

"the 2009 Act" means the Marine and Coastal Access Act 2009(2);

"authorised deposits" means the substances and articles specified in paragraph 4 of Part 1 of this licence;

"authorised scheme" means Work No. 4 described in paragraph 3 of Part 1 of this licence or any part of that work;

"cable protection" means measures for cable crossings and where cable burial is not possible due to ground conditions, to protect cables and prevent loss of seabed sediment by use of grout bags, protective aprons, mattresses, flow energy dissipation (frond) devices or rock and gravel dumping;

"Cefas" means the Centre for Environment, Fisheries and Aquaculture Science or any successor body to its function;

"commence" means the first carrying out of any part of the licensed activities save for pre-construction surveys and monitoring and "commenced" and "commencement" must be construed accordingly;

"condition" means a condition in Part 2 of this licence;

"Defence Infrastructure Organisation Safeguarding" means Ministry of Defence Safeguarding, Defence Infrastructure Organisation, Kingston Road, Sutton Coldfield, West Midlands B75 7RL and any successor body to its functions;

"East Anglia ONE Offshore Wind Farm" means the East Anglia ONE offshore wind farm authorised by the East Anglia ONE Order;

"East Anglia ONE Order" means the East Anglia ONE Offshore Wind Farm Order 2014(**3**) as amended by the East Anglia ONE Offshore Wind Farm (Corrections and Amendments) Order 2016(**4**);

"enforcement officer" means a person authorised to carry out enforcement duties under Chapter 3 of the 2009 Act;

^{(1) 2004} c.20.
(2) 2009 c.23.

⁽²⁾ 2009 c.23. (3) S.I. 2014/1599.

⁽⁴⁾ S.I. 2016/447.

"environmental statement" means the document certified as the environmental statement by the Secretary of State for the purposes of the Order;

"habitat of principal importance" means a habitat type designated pursuant to section 41 of the Natural Environment and Rural Communities Act 2006(**5**)

"in principle monitoring plan" means the document certified as the in principle monitoring plan by the Secretary of State for the purposes of the Order;

"Kingfisher Fortnightly Bulletin" means the bulletin published by the Humber Seafood Institute or such other alternative publication approved in writing by the MMO for the purposes of this licence;

"LAT" means lowest astronomical tide;

"licensed activities" means the activities specified in Part 1 of this licence;

"maintain" includes inspect, upkeep, repair, adjust, and alter and further includes remove, reconstruct and replace (but only in relation to any of the ancillary works in Part 2 of Schedule 1 (ancillary works) to the Order and any component part of any wind turbine generator, offshore electrical station, accommodation platform or meteorological mast described in Part 1 of Schedule 1 (authorised development) to the Order not including the alteration, removal or replacement of foundations), to the extent assessed in the environmental statement; and "maintenance" must be construed accordingly;

"Marine Management Organisation" or "MMO" means the body created under the 2009 Act which is responsible for the monitoring and enforcement of this licence;

"MCA" means the Maritime and Coastguard Agency;

"mean high water springs" or "MHWS" means the highest level which spring tides reach on average over a period of time;

"notice to mariners" means a notice issued by the undertaker to mariners to inform them of issues that affect the safety of navigation;

"offshore cables" means any Alternating Current (AC) or Direct Current (DC) cables offshore and includes fibre optic cables either within the cable or laid alongside;

"offshore Order limits" means the limits shown on the works plan within which the authorised scheme may be carried out, whose grid coordinates are set out in paragraph 5 of Part 1 of this licence;

"the Order" means the East Anglia THREE Offshore Wind Farm Order 2017;

"outline offshore operations and maintenance plan" means the document certified as the outline offshore operations and maintenance plan by the Secretary of State for the purposes of the Order;

"outline written scheme of investigation (offshore)" means the document certified as the outline written scheme of investigation (offshore) by the Secretary of State for the purposes of the Order;

"single offshore phase" means carrying out all offshore works as a single construction operation;

"Trinity House" means the Corporation of Trinity House of Deptford Strond;

"two offshore phases" means carrying out the offshore works as two separate construction operations pursuant to the deemed marine licences set out in schedules 10, 12 and 14 (Licence 1 - Phase 1) of the Order and schedules 11, 13 and 15 (Licence 2 - Phase 2) of the Order respectively;

^{(5) 2006} c.16.

"UK Hydrographic Office" means the UK Hydrographic Office of Admiralty Way, Taunton, Somerset, TA1 2DN;

"undertaker" means East Anglia THREE Limited;

"vessel" means every description of vessel, however propelled or moved, and includes a nondisplacement craft, a personal watercraft, a seaplane on the surface of the water, a hydrofoil vessel, a hovercraft or any other amphibious vehicle and any other thing constructed or adapted for movement through, in, on or over water and which is at the time in, on or over water;

"Work No. 2" means the offshore electrical stations;

"works plan" means the plan certified as the works plan by the Secretary of State for the purposes of the Order.

(2) A reference to any statute, order, regulation or similar instrument is construed as a reference to a statute, order, regulation or instrument as amended by any subsequent statute, order, regulation or instrument or as contained in any subsequent re-enactment.

(3) Unless otherwise indicated—

- (a) all times are taken to be Greenwich Mean Time (GMT);
- (b) all co-ordinates are taken to be latitude and longitude degrees and minutes to two decimal places.

(4) Except where otherwise notified in writing by the relevant organisation, the primary point of contact with the organisations listed below and the address for returns and correspondence are—

(a) Marine Management Organisation

Offshore Marine Licensing

Lancaster House

Hampshire Court

Newcastle Business Park

Newcastle upon Tyne

NE4 7YH

Tel: 0300 123 1032;

(b) Marine Management Organisation (local office)

Marine Environment Team Pakefield Road Lowestoft Suffolk NR33 0HT;

(c) Trinity House Tower Hill

London

EC3N 4DH

Tel: 020 7481 6900;

 (d) The United Kingdom Hydrographic Office Admiralty Way Taunton Somerset

TA1 2DN Tel: 01823 337 900;

- (e) Maritime and Coastguard Agency Navigation Safety Branch Bay 2/20, Spring Place 105 Commercial Road Southampton SO15 1EG Tel: 020 3817 2433;
 (2) Contemporation Figure 1 (2019)
- (f) Centre for Environment, Fisheries and Aquaculture Science

Pakefield Road Lowestoft Suffolk NR33 0HT

Tel: 01502 562 244;

(g) Natural England

Area 1C, Nobel House 17 Smith Square London SW1P 2AL

Tel: 0300 060 4911;

(h) Historic England
Eastgate Court
195-205 High Street
Guildford
GU1 3EH
Tel: 01483 252 059.

Details of licensed marine activities

2. Subject to the licence conditions, this licence authorises the undertaker (and any agent or contractor acting on their behalf) to carry out the following licensable marine activities under section 66(1) of the 2009 Act—

- (a) the deposit at sea of the substances and articles specified in paragraph 4 below;
- (b) the construction of works in or over the sea and/or on or under the sea bed;
- (c) the removal of sediment samples for the purposes of informing environmental monitoring under this licence during pre-construction, construction and operation; and
- (d) the disposal of up to 73,746.5 m³ of inert material of natural origin within the offshore Order limits produced during construction drilling or seabed preparation for foundation works and cable sandwave preparation works at disposal site reference HU212 within the extent of the Order limits seaward of MHWS.
- 3. Such activities are authorised in relation to the construction, maintenance and operation of-

(1) Work No. 4 (phase 1) – up to two cables to connect Work No. 2 with the East Anglia ONE Offshore Wind Farm.

(2) In connection with such Work No. 4 and to the extent that it does not otherwise form part of any such work, further associated development comprising such other works as may be necessary or expedient for the purposes of or in connection with the relevant part of the authorised scheme and which fall within the scope of the work assessed by the environmental statement and the provisions of this licence.

(3) In connection with such Work No. 4, ancillary works within the Order limits which have been subject to an environmental impact assessment recorded in the environmental statement comprising—

- (a) temporary landing places, moorings or other means of accommodating vessels in the construction and/ or maintenance of the authorised scheme; and
- (b) marking buoys, beacons, fenders and other navigational warning or ship impact protection works.
- 4. The substances or articles authorised for deposit at sea are—
 - (a) iron and steel, copper and aluminium;
 - (b) stone and rock;
 - (c) concrete;
 - (d) sand and gravel;
 - (e) plastic and synthetic;
 - (f) material extracted from within the offshore Order limits during construction drilling and seabed preparation for foundation works and cable sandwave preparation works; and
 - (g) marine coatings, other chemicals and timber.
- 5. The grid coordinates for the authorised scheme are specified below—

Point	Latitude (DMS)	Longitude (DMS)	Point	Latitude (DMS)	Longitude (DMS)
1	52° 14′ 1.882′ N	' 2° 26' 45.354" E	30	52° 21′ 19.206″ N	2° 46′ 2.318″ E
2	52° 13 59.088″ N	' 2° 25' 25.766" E	31	52° 21' 17.723" N	2° 46′ 1.395″ E
3	52° 18′ 50.89′ N	′2° 26′ 0.71″ E	32	52° 21' 16.279" N	2° 46′ 0.316″ E
4	52° 19 10.175″ N	' 2° 27' 36.407" E	33	52° 21' 14.879" N	2° 45′ 59.085″ E
5	52° 21 17.057″ N	' 2° 29' 38.731" E	34	52° 21′13.536″ N	2° 45′ 57.708″ E
6	52° 21 17.284″ N	' 2° 29' 40.473" E	35	52° 21' 12.247" N	2° 45′ 56.189″ E
7	52° 21 19.235″ N	' 2° 29' 57.051" E	36	52° 21' 11.884" N	2° 45′ 55.697″ E
8	52° 21 19.717″ N	′ 2° 30′ 12.848″ E	37	52° 20' 39.779" N	2° 35′ 43.596″ E

Point	Latitude Lon (DMS) (DM	gitude 1S)	Point	Latitude (DMS)	Longitude (DMS)
9	52° 21′ 2°3 19.145″ N	1′2.229″ E	38	52° 19' 21.004" N	2° 35′ 42.287″ E
10	52° 21′ 2° 3 19.548″ N E	1′ 49.797″	39	52° 19′ 19.7″ N	2° 35′ 42.202″ E
11	52° 21′ 2° 3 25.052″ N E	4' 13.842"	40	52° 19′ 18.12″ N	2° 35′ 41.945″ E
12	52° 21′ 2° 3 53.636″ N E	4' 13.872"	41	52° 19' 16.554" N	2° 35′ 41.519″ E
13	52° 25′ 2° 34 31.271″ N	4′ 8.916″ E	42	52° 19′ 15.01″ N	2° 35° 40.927″ E
14	52° 25′ 2° 34 56.467″ N	4′ 8.342″ E	43	52° 19′ 13.49″ N	2° 35′ 40.172″ E
15	52° 27′ 2° 34 57.917″ N	4′ 5.046″ E	44		2° 35′ 39.255″ E
16	52° 27′ 2° 4 48.319″ N E	4' 29.313"	45	52° 19′ 10.56″ N	2° 35′ 38.183″ E
17	52° 30′ 2° 44 36.608″ N	4′ 41.63″ E	46	52° 19′ 9.16″ N	2° 35′ 36.958″ E
18	52° 31′ 2° 4 32.077″ N E	4' 38.805"	47	52° 19′ 7.813″ N	2° 35′ 35.587″ E
19	52° 31′ 32.11″ 2° 4 N E	4′ 38.806″	48	52° 19′ 6.524″ N	2° 35′ 34.075″ E
20	52° 45′ 6.908″ 2° 4 N E	4' 40.427"	49	52° 19′ 5.297″ N	2° 35′ 32.429″ E
21	52° 45′ 10.57″ 2° 4 N E	5' 33.773"	50	52° 19′ 4.141″ N	2° 35′ 30.655′ E
22	52° 46′ 3° 2′ 18.078″ N	15.841″ E	51	52° 19′ 3.799″ N	2° 35′ 30.087″ E
23	52° 30′ 2° 4 20.027″ N E	8' 33.266"	52	52° 18′ 18.9″ N	2° 34′ 13.648″ E
24	52° 26′2°4 58.466″ N E	5' 50.653"	53	52' 18' 15.833" N	2° 34′ 13.645″ E
25	52° 21′ 2°40 27.702″ N	6′ 4.456″ E	54		2° 33′ 46.245″ E
26	52° 21′ 2° 40 25.412″ N	5′ 4.374″ E	55		2° 33′ 38.948″ E
27	52° 21′ 2° 40 23.836″ N	6′ 4.11″ E	0	52° 21′ 49.262″ N	2° 44′ 44.274″ E
28	52° 21′ 22.27″ 2° 40 N	6′ 3.678″ E	1		2° 44′ 31.396″ E

Point	Latitude (DMS)	Longitude (DMS)	Point	Latitude (DMS)	Longitude (DMS)
29	52° 2 20.725″ N	21′2°46′3.08″E	2	52° 27' 8.503" N	2° 35′ 52.305″ E
			3	52° 21' 19.757" N	2° 35′ 44.827″ E

6. This licence remains in force until the authorised scheme has been decommissioned in accordance with a programme approved by the Secretary of State under section 106 of the 2004 Act, including any modification to the programme under section 108, and the completion of such programme has been confirmed by the Secretary of State in writing.

7. The provisions of section 72 of the 2009 Act apply to this licence except that the provisions of section 72(7) relating to the transfer of the licence only apply to a transfer not falling within article 5 (benefit of the Order).

8. With respect to any condition which requires the licensed activities be carried out in accordance with the plans, protocols or statements approved under this Schedule, the approved details, plan or scheme are taken to include any amendments that may subsequently be approved in writing by the MMO.

9. Any amendments to or variations from the approved plans, protocols or statements must be minor or immaterial where it has been demonstrated that the subject matter of the approval sought is unlikely to give rise to any materially new or materially different environmental effects from those assessed in the environmental statement.

PART 2

Conditions

Design parameters

1. The total length of the cables and the volume of their cable protection must not exceed the following—

Work	Length	Cable protection
Work No. 4 (interconnection)	190 kilometres	23,980 m ³

Notifications and inspections

2.—(1) The undertaker must ensure that—

- (a) a copy of this licence (issued as part of the grant of the Order) and any subsequent amendments or revisions to it is provided to—
 - (i) all agents and contractors notified to the MMO in accordance with condition 8; and
 - (ii) the masters and transport managers responsible for the vessels notified to the MMO in accordance with condition 8;
- (b) within 28 days of receipt of a copy of this licence those persons referred to in paragraph (a) above must provide a completed confirmation form to the MMO confirming receipt of this licence.

(2) Only those persons and vessels notified to the MMO in accordance with condition 8 are permitted to carry out the licensed activities.

- (3) Copies of this licence must also be available for inspection at the following locations—
 - (a) the undertaker's registered address;
 - (b) any site office located at or adjacent to the construction site and used by the undertaker or its agents and contractors responsible for the loading, transportation or deposit of the authorised deposits; and
 - (c) on board each vessel or at the office of any transport manager with responsibility for vessels from which authorised deposits or removals are to be made.

(4) The documents referred to in sub-paragraph (1)(a) must be available for inspection by an authorised enforcement officer at the locations set out in sub-paragraph (3)(b) above.

(5) The undertaker must provide access, and if necessary appropriate transportation, to the offshore construction site or any other associated works or vessels to facilitate any inspection that the MMO considers necessary to inspect the works during construction and operation of the authorised scheme.

(6) The undertaker must inform the MMO Coastal Office in writing at least five days prior to the commencement of the licensed activities or any part of them, and within five days of completion of the licensed activities.

(7) The undertaker must inform the Kingfisher Information Service of Seafish by email to kingfisher@seafish.co.uk of details regarding the vessel routes, timings and locations relating to the construction of the authorised scheme or relevant part—

- (a) at least ten days prior to the commencement of offshore activities, for inclusion in the Kingfisher Fortnightly Bulletin and offshore hazard awareness data; and
- (b) on completion of construction of all offshore activities.

Confirmation of notification must be provided to the MMO within five days.

(8) A local notice to mariners must be issued at least ten days prior to the commencement of the licensed activities or any part of them advising of the start date of Work No. 4 and the expected vessel routes from the construction ports to the relevant location and the route of the subsea cables. Copies of all notices must be provided to the MMO and UKHO within five days.

(9) The notices to mariners must be updated and reissued at weekly intervals during construction activities and at least five days before any planned operations and maintenance works and supplemented with VHF radio broadcasts agreed with the MCA in accordance with the construction programme approved under condition 6(1)(b). Copies of all notices must be provided to the MMO and UKHO within five days.

(10) The undertaker must notify the UK Hydrographic Office both of the commencement (within ten days), progress and completion of construction (within ten days) of the licensed activities in order that all necessary amendments to nautical charts are made and the undertaker must send a copy of such notifications to the MMO.

(11) In case of damage to, or destruction or decay of, the authorised scheme seaward of MHWS or any part thereof the undertaker must as soon as possible and no later than 24 hours following the undertaker becoming aware of any such damage, destruction or decay, notify MMO, MCA, Trinity House and the UK Hydrographic Office.

Aids to navigation

3.—(1) The undertaker must during the whole period from commencement of the licensed activities to completion of decommissioning seaward of MHWS exhibit such lights, marks, sounds,

signals and other aids to navigation, and to take such other steps for the prevention of danger to navigation as Trinity House may from time to time direct.

(2) The undertaker must during the period from the start of construction of the authorised scheme to completion of decommissioning seaward of MHWS keep Trinity House and the MMO informed of progress of the authorised scheme seaward of MHWS including the following—

- (a) notice of commencement of construction of the authorised scheme within 24 hours of commencement having occurred;
- (b) notice within 24 hours of any aids to navigation being established by the undertaker; and
- (c) notice within five days of completion of construction of the authorised scheme.

(3) The undertaker must provide reports to Trinity House on the availability of aids to navigation in accordance with the frequencies set out in the aids to navigation management plan agreed pursuant to condition 6(1)(j) using the reporting system provided by Trinity House.

(4) The undertaker must during the whole period from commencement of the licensed activities to completion of decommissioning seaward of MHWS notify Trinity House and the MMO of any failure of the aids to navigation and the timescales and plans for remedying such failures, as soon as possible and no later than 24 hours following the undertaker becoming aware of any such failure.

(5) In the event that the provisions of condition 2(11) are invoked, the undertaker must lay down such buoys, exhibit such lights and take such other steps for preventing danger to navigation as directed by Trinity House. Chemicals, drilling and debris

4.—(1) Unless otherwise agreed in writing by the MMO all chemicals used in the construction of the authorised scheme must be selected from the List of Notified Chemicals approved for use by the offshore oil and gas industry under the Offshore Chemicals Regulations 2002 (as amended).

(2) The undertaker must ensure that any coatings/treatments are suitable for use in the marine environment and are used in accordance with guidelines approved by Health and Safety Executive and the Environment Agency Pollution Prevention Control Guidelines.

(3) The storage, handling, transport and use of fuels, lubricants, chemicals and other substances must be undertaken so as to prevent releases into the marine environment, including bunding of 110% of the total volume of all reservoirs and containers.

(4) The undertaker must inform the MMO of the location and quantities of material disposed of each month under the Order, by submission of a disposal return by 31 January each year for the months August to January inclusive, and by 31 July each year for the months February to July inclusive.

(5) The undertaker must ensure that only inert material of natural origin, produced during the drilling installation of or seabed preparation for foundations, and drilling mud is disposed of within site disposal reference HU212 within the extent of the Order limits seaward of MHWS. Any other materials must be screened out before disposal at this site.

(6) The undertaker must ensure that any rock material used in the construction of the authorised scheme is from a recognised source, free from contaminants and containing minimal fines.

(7) In the event that any rock material used in the construction of the authorised scheme is misplaced or lost below MHWS, the undertaker must report the loss to the District Marine Office within 48 hours and if the MMO reasonably considers such material to constitute a navigation or environmental hazard (dependent on the size and nature of the material) the undertaker must endeavour to locate the material and recover it.

(8) The undertaker must ensure that no waste concrete slurry or wash water from concrete or cement works are discharged into the marine environment. Concrete and cement mixing and washing areas should be contained to prevent run off entering the water through the freeing ports.

(9) The undertaker must ensure that any oil, fuel or chemical spill within the marine environment is reported to the MMO, Marine Pollution Response Team in accordance with the marine pollution contingency plan agreed under condition 6(1)(d)(i).

(10) All dropped objects must be reported to the MMO using the Dropped Object Procedure Form as soon as reasonably practicable and in any event within 24 hours of the undertaker becoming aware of an incident. On receipt of the Dropped Object Procedure Form, the MMO may require relevant surveys to be carried out by the undertaker (such as side scan sonar) if reasonable to do so and the MMO may require obstructions to be removed from the seabed at the undertaker's expense if reasonable to do so.

Force majeure

5.—(1) If, due to stress of weather or any other cause the master of a vessel determines that it is necessary to deposit the authorised deposits within or outside of the Order limits because the safety of human life and/or of the vessel is threatened, within 48 hours full details of the circumstances of the deposit must be notified to the MMO.

(2) The unauthorised deposits must be removed at the expense of the undertaker unless written approval is obtained from the MMO.

Pre-construction plans and documentation

6.—(1) The licensed activities or any part of those activities must not commence until the following (as relevant to that part) have been submitted to and approved in writing by the MMO—

- (a) A design plan at a scale of between 1:25,000 and 1:50,000, including detailed representation on the most suitably scaled admiralty chart, to be agreed in writing with the MMO in consultation with Trinity House and the MCA which shows—
 - (i) the length and arrangement of all cables comprising Work No. 4;
 - (ii) a plan showing the indicative programming of particular works as set out in the indicative programme to be provided under sub-paragraph 6(1)(b)(iv); and
 - (iii) any exclusion zones/micrositing requirements identified in any mitigation scheme pursuant to sub-paragraph 6(1)(h);

to ensure conformity with the description of Work No. 4 and compliance with condition 1 above.

- (b) A construction programme and monitoring plan (which accords with the in principle monitoring plan) to include details of—
 - (i) the proposed construction start date;
 - (ii) proposed timings for mobilisation of plant delivery of materials and installation works and whether such works are to be carried out as a single offshore phase or as two offshore phases;
 - (iii) proposed pre-construction surveys, baseline report format and content, construction monitoring, post-construction monitoring and related reporting in accordance with sub-paragraph 6(1)(g) and conditions 9, 10 and 11; and
 - (iv) an indicative written construction programme for all cables comprised in the works at paragraph 3(1) of Part 1 (licensed marine activities) of this Schedule (insofar as not shown in paragraph (ii) above);

with details pursuant to paragraph (iii) above to be submitted to the MMO in accordance with the following—

- (aa) at least four months prior to the first survey, detail of the pre-construction surveys and an outline of all proposed monitoring;
- (bb) at least four months prior to construction, detail on construction monitoring;
- (cc) at least four months prior to commissioning, detail of post-construction (and operational) monitoring;

unless otherwise agreed in writing with the MMO.

- (c) A construction method statement in accordance with the construction methods assessed in the environmental statement and including details of—
 - (i) cable installation, including cable landfall and cable protection;
 - (ii) contractors;
 - (iii) vessels and vessels transit corridors, which minimises disturbance to red-throated diver; and
 - (iv) associated and ancillary works.
- (d) A project environmental management plan covering the period of construction and operation to include details of—
 - (i) a marine pollution contingency plan to address the risks, methods and procedures to deal with any spills and collision incidents of the authorised scheme in relation to all activities carried out;
 - (ii) a chemical risk assessment to include information regarding how and when chemicals are to be used, stored and transported in accordance with recognised best practice guidance;
 - (iii) waste management and disposal arrangements;
 - (iv) the appointment and responsibilities of a fisheries liaison officer;
 - (v) a fisheries liaison and coexistence plan to ensure relevant fishing fleets are notified of commencement of licensed activities pursuant to condition 2 and to address the interaction of the licensed activities with fishing activities; and
 - (vi) procedures to be adopted within vessels transit corridors to minimise disturbance to red-throated diver.
- (e) A scour protection management and cable protection plan providing details of the need, type, sources, quantity and installation methods for scour protection and cable protection, which plan must be updated and resubmitted for approval if changes to it are proposed following cable laying operations.
- (f) A cable specification, installation and monitoring plan, to include—
 - (i) technical specification of offshore cables below MHWS, including a desk-based assessment of attenuation of electro-magnetic field strengths, shielding and cable burial depth in accordance with industry good practice;
 - (ii) a detailed cable laying plan for the Order limits, incorporating a burial risk assessment to ascertain suitable burial depths and cable laying techniques, including cable protection; and
 - (iii) proposals for monitoring offshore cables including cable protection during the operational lifetime of the authorised scheme which includes a risk based approach to the management of unburied or shallow buried cables.
- (g) A written scheme of archaeological investigation in relation to the offshore Order limits seaward of mean low water, which must be submitted at least 6 months prior to commencement of the licensed activities and must accord with the outline written scheme

of investigation (offshore) and industry good practice, in consultation with the statutory historic body to include—

(i) details of responsibilities of the undertaker, archaeological consultant and contractor;

- (ii) a methodology for further site investigation including any specifications for geophysical, geotechnical and diver or remotely operated vehicle investigations;
- (iii) archaeological analysis of survey data, and timetable for reporting, which is to be submitted to the MMO within four months of any survey being completed;
- (iv) delivery of any mitigation including, where necessary, identification and modification of archaeological exclusion zones;
- (v) monitoring of archaeological exclusion zones during and post construction;
- (vi) a requirement for the undertaker to ensure that a copy of any agreed archaeological report is deposited with the National Record of the Historic Environment, by submitting a Historic England OASIS (Online Access to the Index of archaeological investigations') form with a digital copy of the report within six months of completion of construction of the authorised scheme, and to notify the MMO that the OASIS form has been submitted to the National Record of the Historic Environment within two weeks of submission;
- (vii) a reporting and recording protocol, including reporting of any wreck or wreck material during construction, operation and decommissioning of the authorised scheme; and
- (viii) a timetable for all further site investigations, which must allow sufficient opportunity to establish a full understanding of the historic environment within the offshore Order Limits and the approval of any necessary mitigation required as a result of the further site investigations prior to commencement of licensed activities.
- (h) A mitigation scheme for any habitats of principal importance identified by the survey referred to in condition 9(2)(a) and in accordance with the in principle monitoring plan.
- (i) An offshore operations and maintenance plan, in accordance with the outline offshore operations and maintenance plan, to be submitted to the MMO at least four months prior to commencement of operation of the licensed activities and to provide for review and resubmission every three years during the operational phase.
- (j) An aids to navigation management plan to be agreed in writing by the MMO following consultation with Trinity House, to include details of how the undertaker will comply with the provisions of condition 3 for the lifetime of the authorised scheme.

(2) Pre-construction archaeological investigations and pre-commencement material operations which involve intrusive seabed works must only take place in accordance with a specific written scheme of investigation which is itself in accordance with the details set out in the outline offshore written scheme of investigation, and which has been submitted to and approved by the MMO.

7.—(1) Any archaeological reports produced in accordance with condition 6(1)(g)(iii) are to be agreed with the statutory historic body.

(2) Each programme, statement, plan, protocol or scheme required to be approved under condition 6 must be submitted for approval at least four months prior to the intended commencement of licensed activities, except where otherwise stated or unless otherwise agreed in writing by the MMO.

(3) No licensed activity may commence until for that licensed activity the MMO has approved in writing any relevant programme, statement, plan, protocol or scheme required to be approved under condition 6. (4) The licensed activities must be carried out in accordance with the approved plans, protocols, statements, schemes and details approved under condition 6, unless otherwise agreed in writing by the MMO.

(5) No part of the authorised scheme may commence until the MMO, in consultation with the MCA, has given written approval of an Emergency Response Co-operation Plan (ERCoP) which includes full details of the plan for emergency, response and co-operation for the construction, operation and decommissioning phases of that part of the authorised scheme in accordance with the MCA recommendations contained within MGN543 "Offshore Renewable Energy Installations (OREIs) – Guidance on UK Navigational Practice, Safety and Emergency Response Issues", and has confirmed in writing that the undertaker has taken into account and, so far as is applicable to that part of the authorised scheme, adequately addressed all MCA recommendations contained within MGN543 and its annexes.

Reporting of engaged agents, contractors and vessels

8.—(1) The undertaker must provide the following information to the MMO—

- (a) the name and function of any agent or contractor appointed to engage in the licensed activities within seven days of appointment; and
- (b) each week during the construction of the authorised scheme a completed Hydrographic Note H102 listing the vessels currently and to be used in relation to the licensed activities.

(2) Any changes to the supplied details must be notified to the MMO in writing prior to the agent, contractor or vessel engaging in the licensed activities.

Pre-construction monitoring and surveys

9.—(1) The undertaker must, in discharging condition 6(1)(b), submit details (which accord with the in principle monitoring plan) for written approval by the MMO in consultation with relevant statutory bodies of proposed pre-construction surveys, including methodologies and timings, and a proposed format and content for a pre-construction baseline report; and

- (a) the survey proposals must specify each survey's objectives and explain how it will assist in either informing a useful and valid comparison with the post-construction position and/or will enable the validation or otherwise of key predictions in the environmental statement; and
- (b) the baseline report proposals must ensure that the outcome of the agreed surveys together with existing data and reports are drawn together to present a valid statement of the preconstruction position, with any limitations, and must make clear what post-construction comparison is intended and the justification for this being required.

(2) The pre-construction surveys referred to in sub-paragraph (1) must, unless otherwise agreed with the MMO, have due regard to, but not be limited to, the need to undertake—

- (a) appropriate surveys to determine the location and extent of any benthic communities/ benthos constituting habitats of principal importance in whole or in part inside the area(s) within the Order limits in which it is proposed to carry out construction works; and
- (b) a full sea floor coverage swath-bathymetry survey that meets the requirements of IHO S44ed5 Order 1a, and side scan sonar, of the area(s) within the Order limits in which it is proposed to carry out construction works including a 500 metre buffer area around the site of each work, inclusive of seabed anomalies or sites of historic or archaeological interest that lie within that 500 metre buffer.

(3) The undertaker must carry out the surveys agreed under sub-paragraph (1) and provide the baseline report to the MMO in the agreed format in accordance with the agreed timetable,

unless otherwise agreed in writing by the MMO in consultation with the relevant statutory nature conservation bodies.

Construction monitoring

10.—(1) The undertaker must, in discharging condition 6(1)(b), submit details (which accord with the in principle monitoring plan) for approval by the MMO in consultation with the relevant statutory nature conservation bodies of any proposed monitoring, including methodologies and timings, to be carried out during the construction of the authorised scheme. The survey proposals must specify each survey's objectives.

(2) The undertaker must carry out the surveys approved under sub-paragraph (1) and provide the agreed reports in the agreed format in accordance with the agreed timetable, unless otherwise agreed in writing with the MMO in consultation with the relevant statutory nature conservation bodies.

Post construction

11.—(1) The undertaker must, in discharging condition 6(1)(b), submit details (which accord with the in principle monitoring plan) for approval by the MMO in consultation with relevant statutory nature conservation bodies of proposed post-construction surveys, including methodologies and timings, and a proposed format, content and timings for providing reports on the results. The survey proposals must specify each survey's objectives and explain how it will assist in either informing a useful and valid comparison with the pre-construction position and/or will enable the validation or otherwise of key predictions in the environmental statement.

(2) The post-construction surveys referred to in sub-paragraph (1) must, unless otherwise agreed with the MMO, have due regard to, but not be limited to, the need to undertake —

- (a) appropriate surveys of any benthic communities/benthos constituting habitats of principal importance in whole or in part inside the area(s) within the Order limits in which construction works were carried out;
- (b) within twelve months of completion of the licensed activities, one full sea floor coverage swath-bathymetry survey that meets the requirements of IHO S44ed5 Order 1a across the area(s) within the Order limits in which construction works were carried out to assess any changes in bedform topography and such further monitoring or assessment as may be agreed to ensure that cables have been buried or protected.

(3) The undertaker must carry out the surveys agreed under sub-paragraph (1) for up to 3 years post-construction, which could be non-consecutive years, and provide the agreed reports in the agreed format in accordance with the agreed timetable, unless otherwise agreed in writing with the MMO in consultation with the relevant statutory nature conservation bodies.

(4) Following installation of cables, the cable monitoring plan required under condition 6(f)(iii) must be updated with the results of the post installation surveys. The plan must be implemented during the operational lifetime of the project and reviewed as specified within the plan, following cable burial surveys, or as instructed by the MMO.

Coordination with East Anglia ONE Offshore Wind Farm

12.—(1) Prior to submission of each of the pre-construction plans and documentation required to be submitted under condition 6(1)(a) to (j) above the undertaker must provide a copy of the relevant plans and documentation to the undertaker of the offshore element of the East Anglia ONE Offshore Wind Farm to enable that undertaker to provide any comments on the plans and documentation.

(2) The undertaker must participate in liaison meetings with the undertaker of the offshore element of the East Anglia ONE Offshore Wind Farm as requested from time to time by the MMO in writing in advance, which meeting will be chaired by the MMO and may consider such matters as are

determined by the MMO relating to the efficient operation of the offshore element of the authorised project and the offshore element of the East Anglia ONE Offshore Wind Farm.